## ADDENDUM NO. 2

## Gregg County Courthouse Roofing Project Phase 1 Bid #2017-703 CCG 1-132-1

## February 21, 2017

General

- Item No. 1: Bid due date and time remains February 24, 2017 at 2:00 p.m., local time.
- Item No. 2: Roof Composition of Area D:

<u>Area D – At Ridge (Approximate Thickness 4-1/2")</u> BUR, 3/4" Approximately Cellular Foam Glass Insulation, 3-3/4" Approximately Concrete Deck

<u>Area D – Near Drain (Approximate Total Thickness 2-1/4")</u> BUR, 3/4" Approximately Cellular Foam Glass Insulation, 1-1/2" Approximately Concrete Deck

## **Specifications**

- Item No. 3: Section 01 77 00 Add Paragraph 1.1.A.9: Provide ACM manifest to Gregg County as part of close-out documents.
- Item No. 4: Section 07 22 00, Paragraph 3.3.D. Revise reference to 1/8" / ft. slope to 1/4" / ft.
- Item No. 5: Section 07 54 19, Paragraph 2.01.A. Revise reference of 60 mil to 80 mil or approved equal.

End of Addendum 2.