BID PROPOSAL (Revision No.1)

COMMISSIONER'S COURT
COUNTY BUILDING
100 WHALEY STREET
LONGVIEW, TX 75606

TRYON ROAD AT HAWKINS PARKWAY PROJECT #2016-620

Proposal of _____, (hereinafter called "Bidder"), a corporation, organized and existing under the laws of the State of _____ a partnership, or an individual doing business as _____(strike out inapplicable terms).

TO THE COUNTY OF GREGG, TEXAS (OWNER):

The undersigned bidder, in response to the Notice to Bidders for the construction of the above project and in conformance with the Information for Bidders; having examined the plans, specifications, related documents and the site of the proposed work; being familiar with all of the conditions relating to the construction of the proposed project, including the availability of materials and labor; hereby proposed to furnish all labor, materials, supplies, equipment, and superintendence necessary for the construction of the project in accordance with the plans, specifications, and contract documents at the unit prices proposed

The undersigned Bidder proposes, acknowledges, and agrees to construct the entire project as shown on the plans, fully in accordance with the requirements of the plans, specifications, and contract documents for the prices included in this Proposal and fully understands and agrees that the various items of material, labor, and construction not specifically enumerated and provided for herein are considered subsidiary to the several items for which this direct payment is specifically provided. Furthermore, the undersigned agrees that one such subsidiary item is the protection, maintenance, repair, or replacement of all underground lines and services, whether shown on the plans or not, all to the full satsifaction of the Engineer and in a timely manner.

BASE BID - PAVING & DRAINAGE

Item No.	Estimated Quantity	Unit	Name of Pay Item Unit Price in Words	Unit Bid Price	Amount Bid
1.	1	LS	Mobilization (TxDOT Item 500) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
2.	1	LS	Traffic Plan for Road Closure _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
3.	8	EA	Mailbox Assemblies (TxDOT Item 560) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
4.	1	LS	Erosion Control BMPs _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
5.	3.5	AC	R-O-W Preparation (TxDOT Item 100) (Pavement-Conc. & HMAC, Culverts, Tree) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $	$ -	$ -
6.	7086	CY	Excavation (TxDOT Item 110) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -

BASE BID - PAVING & DRAINAGE

Item No.	Estimated Quantity	Unit	Name of Pay Item Unit Price in Words	Unit Bid Price	Amount Bid
7.	362	CY	Embankment (TxDOT Item 132) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
8.	1,850	CY	8" Select Fill (PI = 5 to 15, LL ≤ 40) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
9.	356	SF	8" Limestone Flexbase Temporary Driveway _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
10.	2,572	CY	Limestone Flexbase (TxDOT Item 247) Grade 2 Type A or C _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
11.	283	GAL	Prime Coat (MC30 @ 0.2 gal/SY, ITEM _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
12.	9415	SF	8" Concrete Pavement (3600 psi@ 28 Days) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -

BASE BID - PAVING & DRAINAGE

Item No.	Estimated Quantity	Unit	Name of Pay Item Unit Price in Words	Unit Bid Price	Amount Bid
13.	447	LF	6" Concrete Integral Curb _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
14.	2614	SF	6" Raised Conc Median - 4" Thick Flatwork _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
15.	1,466	TON	4" Type D HMAC Pavement w/ Tackcoat _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
16.	3928	SF	Residential Drwy (2" HMAC on 6" _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
17.	2,376	LF	18" Curb and Gutter _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
18.	1	EA	10" Concrete Curb Inlet _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -

BASE BID - PAVING & DRAINAGE

Item No.	Estimated Quantity	Unit	Name of Pay Item Unit Price in Words	Unit Bid Price	Amount Bid
19.	76	LF	18" HDPE Storm Drain Pipe _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
20.	1	EA	18" HDPE Fittings - 45° Bend _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
21.	174	LF	18" CL III RCP w/ Filter Fabric Joints _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
22.	17	EA	18" S.E.T. w/1:4 Slopes _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
23.	32	LF	15" CGMP Culvert Pipe _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
24.	2	EA	15" S.E.T. w/1:4 Slopes _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -

BASE BID - PAVING & DRAINAGE

Item No.	Estimated Quantity	Unit	Name of Pay Item Unit Price in Words	Unit Bid Price	Amount Bid
25.	24	SY	12" Gabion Mattress w/ Filter Fabric _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
26.	28	EA	Directional Arrows, Words, Stop Bars _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
27.	890	LF	4" Reflective Lane Striping (yellow) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
28.	4,835	LF	4" Reflective Lane Striping (white) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
29.	400	LF	12" Wide Reflective Diagonal Stripe Bars (Yellow) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
30.	10	EA	Signage (Stop, Yield, etc. per MUTCD) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -

BASE BID - PAVING & DRAINAGE

Item No.	Estimated Quantity	Unit	Name of Pay Item Unit Price in Words	Unit Bid Price	Amount Bid
31.	17	STA (Class I)	Furnishing and Placement of 4" of Topsoil _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
32.	6001	SY	Commmon Bermuda Solid Sod (Item 162) _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ -	$ -
33.	1	LS	Miscellaneous Allowance _____ Dollars and _____ Cents Per Unit Breakdown: Labor/Equip $ Material $	$ 10,000.00	$ 10,000.00

BID SUMMARY

TOTAL BASE BID
(Words and Figures)

_____
_____ DOLLARS
_____ CENTS

$ -

TOTAL BASE BID FOR MATERIALS AND EQUIPMENT
INCORPORATED INTO PROJECT
(Words and Figures)

_____
_____ DOLLARS
_____ CENTS

$ -

GREGG COUNTY, TEXAS

Project Name: **TRYON ROAD AT HAWKINS PARKWAY PROJECT**
BID #2016-620

TOTAL MATERIALS COST: _____

TOTAL SERVICES COST: _____

TOTAL CONTRACT PRICE:_____

NOTES:

1. The total materials cost plus the total services costs must equal the amount shown for the total contract price.

2. Only the **selected contractor** will be required to complete Materials and Equipment incorporated in the project within two days of award of contract and prior to execution of Agreement with Gregg County. Complete the Sales Tax Exemption form, ST-1.

The undersigned Bidder hereby agrees to begin work under the contract on or before the date to be specified in the written Notice to Proceed and to fully complete the project within _____ consecutive calendar days. The undersigned Bidder further agrees to pay, as liquidated damages, the sum of **$500.00** for each consecutive calendar day thereafter as provided in Item 23 of the Bid Instructions/Requirements.

The undersigned Bidder has contacted, within 72 hours prior to this bid opening, the Purchasing office and has determined that all Addenda are as follows:

Addendum No. 1, Dated: _____

Addendum No. 2, Dated: _____

The undersigned Bidder acknowledges and agrees that this Proposal shall be good and may not be withdrawn for a period of 60 calendar days from the date of this bid opening.

The undersigned Bidder is obligated to and shall show accurate unit prices as well as total amounts, and agrees that in the case of ambiguity between unit prices and total amounts or in the case of any other ambiguity the Owner may interpret an ambiguity in a manner most advantageous to the Owner or reject the bid.

The undersigned Bidder further acknowledges and agrees that a bid that has been opened may not be changed for the purpose of correcting an error in the final bid price.

The undersigned Bidder agrees to execute the Contract Agreement and furnish the required Performance Bond, Payment Bond, and Maintenance Bond within 15 calendar days from the date of acceptance of the Proposal.

The undersigned Bidder has attached and made a part of this Proposal a bid security in conformance with Item 7 of the Bid Instructions/Requirements.

Submitted by:

_____	_____
(Signature)	(Firm)
_____	_____
(Name - Typed or Printed)	(Address)
_____	
(Title)	
_____	_____
(Attest - Date)	(City, County, State, Zip Code)
(Corporation Seal)	_____
	(Area Code - Telephone Number)
	_____
	(Fax Number)