GREGG COUNTY BID NO. 14-011
NORTH JAIL 3RD FLOOR ROOF REPLACEMENT - REBID
TUESDAY, SEPTEMBER 9, 2014 at 10:00 a.m.
BID TABULATION

ITEM	QTY	UNIT	DESCRIPTION	**Advanced Roofing Services, Inc. Longview, TX		Hefner Roofing, LLC Pittsburg, TX		Hayes Miller Roofing, Inc. Longview, TX		J. Reynolds & Co., Inc. Saginaw, TX		S. Goodwin Roof Service, LLC Center, TX		Clean Cut Roofing White Oak, TX		Curtis-McKinley Roofing Longview, TX	
1	1	LS	Mobilization.		$ 10,000.00		$ 1,500.00		$ 4,000.00		$ 13,327.30		$ 6,000.00		$ 9,000.00		$ 3,000.00
2	1	LS	Bonds & insurance.		$ 1,846.98		$ 13,200.00		$ 5,595.00		$ 13,327.30		$ 16,000.00		$ 6,000.00		$ 3,500.00
3	1	LS	Remove all existing roofing, expansion joints, flashing, and all other roof related components down to the tapered insulation.		$ 5,400.00		$ 8,500.00		$ 17,000.00		$ 33,318.25		$ 17,000.00		$ 15,000.00		$ 25,000.00
4	1	LS	Disconnect and reconnect roof top A/C units, plumbing, and electrical as required using licensed contractors from the appropriate trade. Replace all blocking and wood runners with new treated wood.		$0.00		$ 1,500.00		$ 1,500.00		$ 5,330.92		$ 6,500.00		$ 4,000.00		$ 1,000.00
5	1,500	SF	Replace defective areas of tapered insulation.	$2.00*	$ 3,000.00	$3.00	$ 4,500.00	$4.25	$ 6,375.00	$2.00	$ 2,998.19	$6.75	$ 10,125.00	$1.50	$ 2,250.00	$3.00	$ 4,500.00
6	15,600	SF	Install 1/4" coverboard in low rise adhesive, installing one layer of self-adhered base sheet, followed by installation of one layer of fiberglass reinforced SBS modified bitumen cap sheet using torch welding techniques.	$4.69	$ 73,049.10	$5.07	$ 79,150.00	$5.57	$ 86,900.00	$2.31	$ 35,983.74	$5.50	$ 85,800.00	$8.33	$ 130,000.00	$9.92	$ 154,750.00
7	1	LS	Replace all flashings including curbs, perimeter flashings, wall flashings, and install two plies of flashing membrane per manufacturer's recommendations.		$ 3,900.00		$ 11,750.00		$ 1,200.00		$ 26,654.60		$ 31,500.00		$ 10,000.00		$ 41,550.00
8	200	LF	Remove and replace wolmanized 2x4s as needed.	$2.00	$ 400.00	$3.00	$ 600.00	$6.00*	$ 1,200.00	$5.00	$ 1,000.00	$3.50	$ 700.00	$8.00	$ 1,600.00	$4.00	$ 800.00
9	1	LS	Remove and replace door threshold and door weatherstripping.		$ 100.00		$ 250.00		$ 500.00		$ 1,332.70		$ 600.00		$ 600.00		$ 500.00
10	1	LS	Miscellaneous Allowance		$ 10,000.00		$ 10,000.00		$ 10,000.00		$ 10,000.00		$ 10,000.00		$ 10,000.00		$ 10,000.00
			TOTAL AMOUNT BID		$ 107,696.08		$ 130,950.00 *		$ 134,270.00		$ 143,273.00		$ 184,225.00		$ 188,450.00		$ 244,600.00

*Error corrected by Hayes Eng.
**Bidder did not acknowledge Addendum No. 1 until after the Bid Opening.

*Error corrected by Hayes Eng.

*Error corrected by Hayes Eng.

HAYES ENGINEERING, INC.
Texas Registered Engineering Firm F-1465

9-9-14

Stanley R. Hayes, P.E.
Principal

STANLEY ROSS HAYES
72141
REGISTERED PROFESSIONAL ENGINEER